CEDERBERG
MUNISIPALITEIT | MUNICIPALITY | uMASIPALA

MUNISIPALITEIT
MUNICIPALITY
UMASIPALA

Meld asb. in u antwoord / In your reply please quote

Verwysing / Reference: Clanwilliam Bulk Electrical Services
Navrae / Enquiries: Hilton Wilson

☎ (027) 482 8000
🖷 (027) 482 1933
✉ hiltonw@cederberg.gov.za
www.cederbergmun.gov.za
Privaatsak/Private Bag X2
Clanwilliam
8135

KANTOOR VAN DIE MUNISIPALE BESTUURDER/
OFFICE OF THE MUNICIAL MANAGER

08 April 2026

Attention : Mr Jurie Jackson

Chief Directorate : Human Settlements
Department of Infrastructure
Western Cape Government
9th Floor, 27 Wale Street
Cape Town
8000

Sir

CLANWILLIAM ELECTRICAL SERVICES: CONFIRMATION OF BULK SERVICES

The estimated electrical demand for the planned housing project is 1 800kVA. A new 66/11kV 10 MVA substation with adequate capacity and fed from Graafwater via a new 66kV line is currently in construction. The planned completion and switch-on of this new substation is June 2026, whereafter adequate capacity will be available.

The internal 11kV networks in Clanwilliam have capacity to accommodate this new project. New pole mounted transformers and/or minisubstations with overhead low voltage networks will be constructed for this new development.

Yours sincerely,

MR. R. DE RIDDER
DIRECTOR TECHNICAL SERVICES